

## 雍江悦庭5、6、8号楼外立面 整改项目施工范围

### 新安装原有石材色（相近颜色）铝单板 工程量汇总表

楼栋	位置	单面面积	合计面积
5号楼	门厅前	21.10	72.82
	门厅后1	33.62	
	门厅后2	18.10	
6号楼	门厅前	23.81	55.17
	门厅后	31.36	
8号楼	第四层	44.88	81.48
	第三层	36.60	

单位：m<sup>2</sup>



5号楼平面拆除及重装范围




门厅前



此面工程量合计:  
 $10.5 \times 2.01 = 21.11 \text{m}^2$

备注: 长度含同一高度位  
置两侧内折宽度



展开宽度:  
 $0.3+0.4+0.03 \times 2+0.05+0.6+0.6=2.01\text{m}$




5号楼平面拆除及重装范围

门厅后1



此面工程量合计:  
 $17.6 \times 1.91 = 33.62 \text{m}^2$

备注: 长度含同一高度位  
置两侧内折宽度



展开宽度:  
 $0.3+0.4+0.03 \times 2+0.05+0.6+0.5=1.91\text{m}$


5号楼平面拆除及重装范围

门厅后2



此面工程量合计:  
 $10 \times 1.81 = 18.1 \text{m}^2$

备注: 长度含同一高度位置  
两侧内折宽度



展开宽度:

$0.3 + 0.4 + 0.03 \times 2 + 0.05 + 0.6 + 0.4 = 1.81 \text{m}$


6号楼平面拆除及重装范围

门厅前



此面工程量合计:  
 $11.85 \times 2.01 = 23.81 \text{m}^2$

备注: 长度含同一高度位置两  
侧内折宽度



展开宽度:

$0.3 + 0.4 + 0.03 \times 2 + 0.05 + 0.6 + 0.6 = 2.01 \text{m}$



6号楼平面拆除及重装范围




门厅后



此面工程量合计：  
 $15.6 \times 2.01 = 31.36 \text{m}^2$

备注：长度含同一高度位置  
两侧内折宽度



展开宽度：  
 $0.3 + 0.4 + 0.03 \times 2 + 0.05 + 0.6 + 0.6 = 2.01 \text{m}$



8号楼平面拆除及重装范围



第四层

长度：29.72m；展开宽度：1.51m

第三层


长度：12.12m；展开宽度：1.51m

长度：12.12m；展开宽度：1.51m



此面工程量合计：  
 $(29.72 + 12.12 \times 2) \times 1.51 = 81.48 \text{m}^2$

备注：长度含同一高度位置  
两侧内折宽度



展开宽度：  
 $0.3 + 0.3 + 0.03 \times 2 + 0.05 + 0.5 + 0.3 = 1.51 \text{m}$

## 安装雨水板 工程量汇总表

楼栋	数量 (块)	单块面积	合计面积
5号楼	31	$0.7*6=4.2$	130.2
6号楼	33	$0.7*6=4.2$	138.6


单位:  $m^2$



5号楼雨水板施工范围



同样位置，总计31层需要  
重做雨水板  
工程量合计：  
 $6*0.7*31=130.2m^2$






6号楼雨水板施工范围



同样位置，总计33层需要  
重做雨水板  
工程量合计：  
 $6*0.7*33=138.6\text{m}^2$



外立面局部补  
真石漆  
工程量汇总表

楼栋	暂估面积 (m <sup>2</sup> )
6号楼	50

